# SCT Barrel Sector Prototype Test Program- Short Term Aims

#### Harness Test.

Installation and evaluation of a single harness & 6 modules.Urgent need to sign off the design for manufacture.

#### Thermal Tests- Repeat

? T across inlet and exhaust with first configuration.
Temperature profile along the stave - 'cooling loop'
Detector temperature during operation.

#### **Mechanical Tests**

Distortion of 'special dummy' module when cooled.Distortion of the cooling loop when cooled.

Configuration 2: Barrel Features & C.D.S.

#### **Barrel Sector Prototype**

•10° tilt angle brackets.

Alumina strip heater modules without clipped copper tab electrical connections – epoxy connections – see next slide
Pre-production prototype 1 cooling loop.

#### **Capacitive Displacement System**

- •A trolley with capacitive sensors measures displacements in all axes on a special alumina dummy.
- •7 sensor heads 'see' the cubic faces.
- •Can be positioned anywhere on the sector.
- •Accurate to 1µm.
- •System traverses Z on fused silica rails.



Lewis Batchelor RAL

SCT Week 10/2002

## Barrel Damage



•At some point 2 pads have been damaged

•Most probably consistent with loss of 2 power supplies.

•Can rotate away from problem for remaining tests at RAL.

•Problem will be repaired before sector goes to Oxford.



## Configuration 2: Environmental Chamber

Large chest freezer equipped with Oxford's thermal Imaging camera and web-cams – see what is happening.
Reduced humidity – NO frosted cooling pipes! Dew point thus far= -22°C with coolant flow at -20 °C
Precise control and data-logging of chamber temperature. -25°C - 0 °C

• Aluminium/Copper faraday cage construction.

•Module DAQ interface.



Faraday Cage in construction

**Barrel Sector Prototype** 



Lewis Batchelor RAL

SCT Week 10/2002

## Configuration 2: Environmental Chamber and Services

Services entry via patch panel - future flexibility.
Cooling loop is electrically isolated from evaporative rig pipework.
Larger bore on evaporative rig exhaust – maximise compressor power.

•PT100 temperature sensors replaced with 'one-wire' system- time for a complete scan <10s



Patch Panels in construction

# Completion of Configuration 2

- •Brackets- no change
- •Alumina Dummy Modules- change electrical connections- in progress.
- •C.D.S. –Installed.
- •New Test Chamber- in progress.
- •Evaporative cooling plant operational.
- •One wire temperature sensor system tested, installation in progress.
- •Harness awaiting cooling loop removal in progress.

#### Estimate all the above will be complete by 13/10/2002

# **Configuration 3**

#### Sector Prototype

•New 11° tilt angle brackets.

#### **Cooling Loop**

•Final design loop – pre-production prototype 2.

•Production shunt shields.

•1 half row of new cooling blocks for electrical modules.

•Final design clips.

#### Modules

•36 alumina dummies, 6 instrumented thermo-mechanical modules, and 6 real modules!

# Evaporative Cooling: Sub-Cooling

The RAL Evaporative rig does not perform well without sub-cooling, i.e. the C3F8 is delivered to the capillary at room temperature.

- During preliminary tests peak mass flow =1.45 g/s
- •inlet/exhaust **?T = 11°C** (120 Watt load)
- With sub-cooling operational mass flow = 2 6 g/s.
- •inlet/exhaust ?T < 1°C
  - 1g/s ~ 100Watts cooling.
- -Evaporation in cooling circuit prior to arrival at the capillary?
- -See Lewis for more detail.

# Evaporative Cooling:No Sub-Cooling and Active Heating

#### Non Sub-Cooled Operation

•An additional compressor in series with the current unit could enable the rig to achieve a high enough pressure to deliver liquid C3F8 to the stave capillaries. Installation is being considered jointly with the RAL Health and Safety department - Pressure specification on CuNi pipe/Evaporative Rig?

#### SCT Cooling Strategy- Exhaust 'Active Heating'

• Evaluation of heater design and control for the above. Installation in progress.

#### **Additional Modifications**

•Michel's group will produce a prototype heat exchanger with 2 inlets and one return tubes brazed along the length about 1.3 m long.

•Liquid flow meter, in addition to the current Gas meter- datalogging/monitoring. Calibration in progress.

# Estimate completion of the necessary modifications by the end of October.

**Active Heater Possibilities** 

![](_page_10_Picture_1.jpeg)

CERN supplied heater- 1m long, 18mm diameter

![](_page_10_Picture_3.jpeg)

Commercially available- 25 cm long, 35mm diameter

![](_page_11_Picture_0.jpeg)

![](_page_11_Picture_1.jpeg)

Gas Flow Meter

Lewis Batchelor RAL

SCT Week 10/2002

## **RAL Evaporative Rig - Schematic**

![](_page_12_Figure_1.jpeg)

### RAL Evaporative Rig – Schematic II

![](_page_13_Figure_1.jpeg)

# Capillary Test

•Aim - Demonstrate the equation, determine the constant, A:

$$P = A \left(\frac{dm}{dt}\right)^{\frac{7}{4}} \frac{L}{ID^{\frac{19}{4}}}$$

Where **?P** = pressure drop across the capillary, dm/dt = mass flow, L=capillary length and ID=Inner diameter of the capillary.

•Define the production capillary parameters for the final SCT cooling system.

•The Capillary test piece is operated when other users (Barrel&End Cap) are not running.

![](_page_14_Picture_6.jpeg)

Capillary test piece in situ -'piggy-backing' the End Cap stave.

# Capillary Test ctd.

•A matrix of capillary IDs and Lengths to be tested.

•The first test capillary is ready – ID=0.8mm L=0.8m.

•30m lengths of ID=0.7mm and ID=1.0mm have arrived so far.

•? P Pressure transducers installed and operational.

•Labview Interface ready and operational.

# RAL SCT Cooling Web Resource

![](_page_16_Picture_1.jpeg)

For more detailed information relating to configurations 1,2 & 3 and any other RAL cooling activities:

http://hepwww.rl.ac.uk/atlassct/B3SectorPrototype/Main.htm